

**FINAL REPORT OF  
GEOTECHNICAL  
INVESTIGATION**

**Rhode Island National Guard**  
**Maintenance Hanger**  
Quonset Air National Guard Base  
North Kingston, Rhode Island

Prepared by:  
NORTHEAST ENGINEERS  
& CONSULTANTS, INC.  
42 Valley Road  
Middletown, Rhode Island 02842

Prepared for:  
The Benham Group, Inc.  
3668 South Geyser Road  
St. Louis, Missouri 63127-1243

March 28, 2001

**TABLE OF CONTENTS**

<b>1.0</b>	<b>INTRODUCTION .....</b>	<b>4</b>
<b>2.0</b>	<b>PROPOSED DEVELOPMENT .....</b>	<b>4</b>
<b>3.0</b>	<b>PURPOSE .....</b>	<b>4</b>
<b>4.0</b>	<b>SCOPE OF WORK .....</b>	<b>5</b>
<b>5.0</b>	<b>FIELD EXPLORATION .....</b>	<b>6</b>
<b>6.0</b>	<b>LABORATORY TESTING .....</b>	<b>6</b>
<b>7.0</b>	<b>SITE CONDITIONS .....</b>	<b>6</b>
	SURFACE CONDITIONS .....	6
	SUBSURFACE CONDITIONS .....	6
	EARTH MATERIALS .....	7
	GROUNDWATER .....	7
<b>8.0</b>	<b>CONCLUSIONS AND RECOMMENDATIONS .....</b>	<b>7</b>
	GENERAL .....	7
	SEISMIC DESIGN .....	8
	LIQUEFACTION .....	8
	SITE PREPARATION AND GRADING .....	8
	GENERAL .....	8
	CLEARING AND GRUBBING .....	8
	SUBGRADE AND PREPARATION OF FILL BOTTOMS .....	9
	FILL MATERIAL REQUIREMENTS .....	9
	FILL PLACEMENT AND COMPACTION REQUIREMENTS .....	9
	TYPES AND FREQUENCY OF FIELD TESTS FOR ENGINEERED COMPACTED FILL .....	9
	UTILITY INSTALLATIONS .....	10
	PILE FOUNDATIONS .....	10
	GENERAL .....	10
	AXIAL CAPACITY .....	11
	PILE INSTALLATION .....	11
	PASSIVE CAPACITY .....	12
	DRAINAGE .....	12
	PAVEMENT DESIGN .....	12
	PLAN REVIEW .....	12

TESTING AND OBSERVATION .....	12
9.0 LIMITS OF INVESTIGATION.....	13
10.0 APPENDICES .....	16

Figure 1- Site Plan

Figures 2, 3 and 4 – Pile Capacity Charts

**APPENDIX A: BORING LOGS AND LAB TEST RESULTS**

## 1.0 INTRODUCTION

This report presents the results of our geotechnical investigation for the proposed new Maintenance Hanger at the Quonset Air National Guard Base in North Kingston, Rhode Island. The facility will be located at the northwest corner of the intersection of Flightline Drive and Hercules Drive on the base. The proposed development and the project location are shown on the Site Plan, Figure 1.

## 2.0 PROPOSED DEVELOPMENT

The project consists of a new maintenance hanger that will be approximately 304 feet long and 190 feet wide. The first Phase of the hanger will consist of the main service bay and a row of maintenance rooms along the rear wall. Phase 2 will consist of additions to each side of the Phase 1 structure that will be occupied by machine shops. A second story to the south addition will contain classrooms and offices.

The total maximum downward reaction at the rigid frame columns of the new hanger is expected to be approximately 283 kips, with column spacing at 25 feet. Maximum uplift reaction is expected to be approximately 92 kips. Maximum floor loads for the shop and office areas are expected to be 300 psf. The maximum tire load for an empty airplane is expected to be 17 kips, with distributed jacking load of 350 psf. The total gross airplane weight is expected to be 175,000 pounds.

The new hanger will have new paved parking areas to the north and south. Two new above ground fire water storage tanks and a pump station will also be constructed to the south and west of the main hanger building. Each water tank will have a capacity of 90,000 gallons and will have a concrete ring foundation. The pump house will be constructed with CMU walls and concrete slab with below grade pits in the corners. The structure will have a total load of about 100 psf.

## 3.0 PURPOSE

The purpose of our investigation is to explore the subsurface conditions at the site in order to develop recommendations for site preparation and foundation design. This report is based on our borings and laboratory testing plus data from our previous geotechnical investigation for improvements to the nearby Squadron Operations Building. We previously submitted a preliminary report dated January 29, 2001, to provide geotechnical information for planning and preliminary structural design. This final report presents our final conclusions and recommendations that either supercede or supplement those in our preliminary report.

## 4.0 SCOPE OF WORK

Our scope of work for this project has consisted of the following tasks:

1. A field exploration program that consisted of drilling, logging and sampling eight deep borings within the proposed hanger location to depths ranging from 38 to 50 feet, except one boring, B-5 that met refusal at a depth of 20 feet. Two deep borings were drilled at the proposed water tank and pump station locations to depths of 46 to 50 feet. Six shallow borings were drilled in the proposed parking areas and hanger apron entrance to depths of about 17 feet.
2. Engineering analyses utilizing the results of the field exploration and our previous investigation of the Squadron Operations Building to develop site preparation and foundation design recommendations.
3. Preparation of this report that summarizes the results of our field exploration, laboratory testing, engineering analyses, and recommendations for the proposed project. The report includes the following:
  - Description of surface and anticipated subsurface conditions.
  - Results of subsurface explorations with a description of the soil and groundwater conditions encountered.
  - Recommendations for earthwork, including site preparation, excavation, and the placing of any required compacted fill.
  - Suitability of on-site soils for use in compacted fills, and recommendations for borrow material, if required.
  - Foundation recommendations including:
    - Allowable vertical bearing capacities and settlement characteristics for the anticipated building loads.
    - Lateral load design parameters for foundations, e.g., the allowable frictional and passive values for bearing materials.
    - Recommendation of remedial measures for any special problems encountered.

## 5.0 FIELD EXPLORATION

Between January 25 and February 16, 2001, a total of ten deep borings and six shallow borings were excavated by our subcontractor Enviro-Tech Drilling, Inc. A representative from our office directed the drilling operations and obtained soil samples for laboratory testing. Logs of the borings are presented in Appendix A. Boring locations are shown on the Site Plan, Figure 1.

## 6.0 LABORATORY TESTING

Our laboratory testing consisted of sieve analyses on six samples obtained from the borings to aid in classification, plus one California Bearing Ratio (CBR) test on a bulk sample of near surface soils for pavement design. A Proctor Compaction curve was also performed on this bulk sample to provide information on maximum dry density and optimum moisture content values for the CBR test, which was performed on a remolded sample compacted to 95% relative compaction to simulate probable pavement subgrade conditions during construction. Our laboratory test results are included in Appendix A.

## 7.0 SITE CONDITIONS

### SURFACE CONDITIONS

The site is currently vacant and covered with grass. The terrain is relatively level, except for a tree covered landscaping mound at the north portion of the site where a parking area is proposed. A paved roadway extends along the east and north sides of the hanger location. An underground storm drain crosses the hanger location.

### SUBSURFACE CONDITIONS

#### *EARTH MATERIALS*

Each boring initially encountered a surface layer of medium dense sand that extended to depths of about 3 to 4 feet. Below this surface layer, each boring except B-6 and B-15 encountered fine to medium grained sand that was loose to very loose and wet and extended to a depth of about 15 to 18 feet. Borings B-6 and B-15 encountered medium dense to dense fine to coarse sand between the surface layer and a depth of about 15 feet. In seven of the 16 borings, primarily those in the southern portion of the site, the loose sand was underlain by a layer of soft peat between depths of 10 and 15 feet. The sand encountered within the upper 10 to 18 feet is likely to be previously placed fill.

Below a depth of 15 to 18 feet, each boring encountered native fine sand and silty sand that varied in consistency from medium dense to very dense. Boring B-1 met refusal at a depth of 38 feet; Borings B-4 and B-7 met refusal at a depth of 48 feet. Shale fragments were encountered at refusal depth in Boring B-4. Boring B-5 met refusal at a depth of only 20 feet; however, this was

most likely due to an isolated cobble or boulder. These subsurface conditions are similar to those encountered at the Squadron Operations Building.

Detailed descriptions of the soils encountered are presented on the boring logs in Appendix A.

### ***GROUNDWATER***

Groundwater was encountered in each boring between depths of 6 to 9 feet, with groundwater at 6 feet in most of the borings. Groundwater levels at the site are expected to fluctuate due to changes in water level and seasonal variations in rainfall, temperature, irrigation, tidal influence, and other factors.

## **8.0 CONCLUSIONS AND RECOMMENDATIONS**

### **GENERAL**

It is our opinion, based on our field exploration, laboratory testing, and engineering analyses, that the site is suitable for the proposed construction when treated in accordance with the recommendations in this report. The primary geotechnical concern is settlement caused by consolidation of the soft peat and loose sands.

The layer of peat and portions of the existing fill are soft and loose and susceptible to compression and consolidation upon the application of structural loads that could result in significant settlement of the ground surface and any overlying structures. These conditions resulted in the nearby Squadron Operations building being constructed on timber piles driven into the medium dense to dense native sands to transfer the structural loads through the compressible zone, thus avoiding the triggering of any significant settlement. Since the project site has similar subsurface conditions, a similar pile foundation is a feasible solution for the proposed hanger and water tanks. To avoid problems with differential settlement, we recommend that the hanger floor be constructed as a structural slab supported by the pile foundation.

Other methods of reducing potential settlement include overexcavation of all loose and soft soils and replacement with compacted engineered fill, or ground modification to strengthen and reduce the compressibility of the soft and loose soils. These options would allow the use of shallow footings rather than piles. Overexcavation is not recommended since the depth of removal would extend well below the groundwater table requiring extensive dewatering and stabilization of the bottom. This option would likely be significantly more expensive than a pile foundation.

Ground modification methods that would be appropriate for the site conditions include jet grouting, vibro-replacement, or soil mixing. Each method involves the injection of grout or stone into the subsurface to strengthen the soft and loose soils. These methods involve specialized equipment and experienced specialty contractors, and are likely to be significantly more expensive than piles.

The proposed pump house will impose structural loads significantly less than the hanger or water tanks, so piles may not be necessary to reduce settlements. Depending on the depth of the structure, the loads may be no greater than the existing overburden stress of the soil. The main concern would be the achievement of a stable bottom of the structure, since it will likely be founded in loose sandy soil close to or below the water table. We can provide further recommendations for the pump house foundation after more design details become available.

### **SEISMIC DESIGN**

For seismic design in accordance with the BOCA Building Code, the recommended site soil profile type is Type S3, giving a site coefficient  $S=0.15$ . The effective peak velocity-related acceleration ( $A_v$ ) and the effective peak acceleration ( $A_a$ ) should both be taken as 0.12 g.

### **LIQUEFACTION**

Liquefaction potential has been found to be the greatest where the groundwater level is shallow and loose fine sand occurs within 50 feet of the ground surface. Liquefaction potential decreases with increasing grain size, clay and gravel content, and soil density, but increases as the seismic ground acceleration and duration of shaking increases. The loose sandy fill in some areas of the site is partially below the ground water table and could be susceptible to liquefaction in a strong earthquake; however the use of a pile foundation will essentially eliminate the liquefaction hazard for the proposed buildings.

### **SITE PREPARATION AND GRADING**

#### ***GENERAL***

This section pertains to demolition, site preparation, incidental buried utility relocation or installation, and grading and excavations required for the project.

#### ***CLEARING AND GRUBBING***

The site should be cleared of all debris and unsuitable or deleterious materials, or structures that conflict with the proposed construction. Utilities in conflict with the proposed construction should be relocated or removed from the site. Excavation should be performed as necessary to remove any loose or disturbed soils, if encountered. The resulting excavations or voids should be treated in a manner acceptable to the geotechnical consultant.

#### ***SUBGRADE AND PREPARATION OF FILL BOTTOMS***

After overexcavation, the exposed bottoms should be observed by the geotechnical consultant to determine if additional overexcavation is required. After the bottoms are approved by the geotechnical engineer, they should be compacted to a minimum relative compaction of 95% based on ASTM D1557. If the bottoms cannot be compacted due to saturated conditions, the bottoms should be covered with a layer of stabilization geotextile followed by a minimum 2 foot



layer of crushed stone to create a stable subgrade before placement of engineered fill. A second layer of geotextile should be placed over the crushed stone before placement of engineered fill. The stabilization layer should be observed by the geotechnical consultant before placing the engineered fill to determine whether a stable subgrade has been achieved, and to assess whether additional stabilization measures are required, such as placement of a layer of additional oversize material or more geotextile.

### ***FILL MATERIAL REQUIREMENTS***

The onsite and any import materials used as engineered fill should consist of inorganic, well-graded non-expansive soils, and have a maximum size of six inches. The existing fill should be suitable, as long as any debris or organic material is removed. The peat beneath the fill is not suitable for fill.

### ***FILL PLACEMENT AND COMPACTION REQUIREMENTS***

Soil used as engineered fill should be moisture conditioned to near optimum moisture content, placed in 12 inch thick loose lifts and compacted to at least 95 percent of the maximum dry density as determined by ASTM D 1557-91. Crushed stone should be placed in layers not more than 2 feet thick and spread evenly to achieve compaction.

### ***TYPES AND FREQUENCY OF FIELD TESTS FOR ENGINEERED COMPACTED FILL***

The geotechnical consultant should be retained to observe and test all engineered compacted fill and backfill placement. The types and frequency of in-place field density tests during placement of engineered compacted fill and frequency of laboratory determinations of maximum density of fill materials should generally be left to the discretion of the geotechnical consultant.

As a general guideline, at least one in-place field density test should be performed for every two feet vertical of fill placed in a single operation, or for every 500 cubic yards of fill placed in a single operation, or for each soil type used, or each single compaction operation. A laboratory Compaction Characteristics Test (ASTM D 1557) will be required when there is a change in the compaction characteristic of the on-site material or import material being used.

### ***UTILITY INSTALLATIONS***

Sides of trenches should be sloped or shored in accordance with OSHA standards. Properly designed trench shields may be used in lieu of shoring. We recommend that excavations less than five feet deep be sloped or protected with portable trench shields. The on site sandy fill soils are susceptible to possible caving, which represents a potential hazard to workmen hunched over for installations of conduits, even in shallow excavations.

Backfill under, around and over buried conduits should be compacted to at least 90 percent of the maximum dry density as determined by ASTM D 1557. Buried utility lines should be provided with bedding as recommended by the project civil engineer, or the utility company or agency that

has jurisdiction. Excavation should be performed as necessary to remove all loose and disturbed soils and unsuitable fill materials

## **PILE FOUNDATIONS**

### ***GENERAL***

The proposed hanger and water tanks should be supported by drilled or driven piles that derive vertical support in the dense native sands beneath the fill and peat layers. Feasible pile options include driven timber piles, driven steel pipe piles, cast-in-place reinforced concrete drilled piles, or pressure-injected footings (PIF), otherwise known as Franki Piles. Timber piles are typically the least expensive type; the one concern would be protection against rot above the water table. Because of their taper, timber piles do not provide much uplift capacity. Steel pipe piles provide higher downward capacity per pile but at higher cost. Steel piles would need protection against corrosion. Drilled cast-in-place concrete piles may need to be cased resulting in significantly higher cost than the driven piles. Steel pipe piles and drilled cast-in-place piles also do not provide much uplift capacity because of the limited adhesion to the steel pipe or casing.

Franki piles are driven cast-in-situ concrete piles that have enlarged bases that can provide high downward and uplift capacities. They are constructed by driving zero-slump batches of concrete through a steel casing with an internal hammer that densifies the surrounding soil. The casing is typically removed as the pile is formed, and steel reinforcement is added if needed, especially if uplift capacity is required. Downward vertical capacity is a function of the diameter, hammer energy, and concrete batch volume. Recommended maximum working loads range from 50 to 300 tons. Once a suitable bearing layer is encountered, the pile installation method can be adjusted to achieve the desired allowable capacity. Uplift capacities are a function of the volume and depth of the enlarged base. Franki piles are the most effective in fine grain sands and silty sands.

Franki piles may be the best choice for the hanger columns due to their relatively high downward and uplift capacities.

The floor of the hanger should consist of a structural slab that is supported by piles. Since no uplift resistance is required and loads are relatively light, timber piles are probably the best choice to support the floor slab.

The water storage tanks should be constructed on mat foundations supported by piles. Timber piles or Franki piles may be appropriate depending on the structural loads. Similarly, either pile type may be suitable for the pump house, if piles are determined to be required, and depending on the load conditions.

### ***AXIAL CAPACITY***

Timber piles are typically limited in capacity to 25 to 30 tons. The capacities of steel pipe piles and drilled cast-in-place piles are limited by the strength of the steel and concrete. Recommended allowable downward axial and uplift capacities of timber piles, steel pipe piles,

and drilled cast-in-place concrete piles are plotted versus depth on Figures 2, 3, and 4, respectively. The capacities for steel pipe piles assume closed-end driven piles, and the capacities for drilled piles assume they are cased for their full length. The allowable downward capacities were calculated applying a safety factor of 3 for dead plus live loads. The weight of the piles may be neglected. Uplift capacities were calculated assuming a safety factor of 2 for wind and seismic loads in combination with dead and live loads.

Standard Franki piles with a nominal shaft diameter of 22 inches should be able to achieve the maximum allowable downward axial load of 200 tons with the base constructed in the native dense sands at depths of 20 feet or deeper. This assumes a safety factor of 3 for dead plus live loads. Allowable uplift capacity is dependent on the pile depth and size of the base. Assuming a base volume of 10 cubic feet, allowable uplift capacities of 24 tons and 72 tons should be achievable for pile depths of 20 feet and 25 feet, respectively. These values assume a safety factor of 2 for dead plus live plus seismic/wind loads. For the site conditions and loading requirements, uncased zero-slump concrete piles with steel reinforcement are recommended.

The allowable bearing values are based on the soil conditions, and the structural design of the piles may govern the final design dimensions. Concrete strength and steel reinforcement shall be the responsibility of the project structural engineer.

The total settlement of the proposed pile foundation is not expected to exceed one-half inch. Differential settlements between two adjacent similarly loaded foundations are not expected to exceed one-quarter inch. Settlements are expected to occur shortly after vertical loads are applied.

#### *PILE INSTALLATION*

Driven piles should be spaced no closer than three times the diameter to achieve the full capacity and to avoid conflict with adjacent piles. We recommend that at least one downward and one uplift load test be performed on each type of pile to confirm design capacities and to develop final installation criteria. Our firm should be allowed to review the pile design and hammer submittal, monitor the load tests, and should provide fulltime monitoring of the pile driving to determine if the design capacities are achieved.

Driven piles should be predrilled through the upper dense fill layer. Drilled piles will probably need to be cased through the loose sandy fill to avoid caving.

#### *PASSIVE CAPACITY*

The allowable lateral passive capacity of piles bearing against the existing fill and native soils may be taken as equivalent to that of a fluid weighing 250 pounds per cubic foot (pcf), to a maximum value of 2,500 psf. These values incorporate a factor of safety of 2.0 and consideration of the "end effect", and should conform to the minimum spacing requirements presented herein. These values may be increased by one-third for wind or seismic loads.

## **DRAINAGE**

The site should be graded to provide for positive drainage away from structures in accordance with the building code and applicable local requirements. Graded pads should slope no less than 2% to drain. Paved areas should slope at least 1% to drain. Concentrated roof and surface drainage from the site should be collected in engineered, non-erosive drainage devices and conducted to a safe point of discharge. The site drainage should be designed by a civil engineer.

## **PAVEMENT DESIGN**

We developed recommendations for pavement design based on information you provided and our field and laboratory testing. The existing near surface soils are silty sands that have a CBR value of 23 when compacted to 95% relative compaction based on ASTM D 1557. We used this value for our recommendations assuming there will be no significant cuts or fills in the pavement areas, or that no imported soils will be used in these areas; otherwise our recommendations may need modification.

The paved parking areas planned for the north and south sides of the hanger should consist of a 3 inch layer of asphalt concrete over 8 inches of aggregate base. The aggregate base and upper 12 inches of subgrade should be compacted to a minimum 95 % relative compaction.

We recommend that the concrete apron entrance to the hanger consist of a 12-inch concrete slab over a 4-inch aggregate base layer, assuming an allowable concrete working stress of 450 psi. The base layer and upper 12 inches of subgrade should be compacted to a minimum 95 % relative compaction.

## **PLAN REVIEW**

The geotechnical consultant should be retained to review grading and foundation plans and specifications to ascertain conformance with site conditions and recommendations presented herein.

## **TESTING AND OBSERVATION**

The geotechnical consultant should be retained to perform on-site construction observations and testing to ascertain that conditions correspond to the findings and conclusions presented herein and that construction conforms generally to the recommendations presented herein. The geotechnical consultant should be called out for testing and observations as indicated in this report and at least for the following:

Full time observation of pile driving operations.

Inspection of all subgrade and fill bottoms following excavation, before scarifying, recompaction and any fill is placed.

Continuous inspection of all temporary construction excavations located closer to existing structures than one and one-half times the depth of excavation, and inspection of all other

temporary construction excavations following excavation, before beginning work near the sides of excavation.

Testing and inspection of all fill placement as discussed under the subsection **Types and Frequency of Field Tests for Engineered Compacted Fill**.

Inspection of all foundation excavations before rebar or concrete is placed.

It is the responsibility of the contractor to coordinate all inspections and testing required by this firm or by other regulatory agencies. We should be given at least 48 hours notice that construction is commencing and no less than 24 hours notice of required geotechnical tests and/or inspections.

## 9.0 LIMITS OF INVESTIGATION

The analyses, conclusions, and recommendations contained in this report are based on site conditions as they existed at the time of our investigation and further assume that the explorations to be representative of the subsurface conditions throughout the site. No warranty is made nor should any be construed that unforeseen geotechnical or geological weakness may not exist between exploratory points or below the depths explored. If different subsurface conditions are observed during construction, we should be promptly notified for review and reconsideration of our recommendations.

This report was prepared for the exclusive use and benefit of the owner, architect, and engineer for evaluating the design of the facility as it relates to certain geotechnical aspects. It should be made available to prospective contractors for information on factual data only, and not as a warranty of subsurface conditions included in this report.

If the proposed development is substantially modified from that which is discussed herein under **Proposed Development**, we should be retained to review the new proposed development to ascertain whether our findings, conclusions, and recommendations remain applicable.

Site conditions can change with time. If more than 18 months have passed since the submittal of this report, we should review the site to determine if our conclusions and recommendations are still applicable.

We recommend that Northeast Engineers & Consultants be retained and given the opportunity to review those portions of the plans and specifications that pertain to foundations and earthwork to ascertain whether they are consistent with the recommendations of this report, and to inspect construction, particularly foundations, shoring, site grading, and earthwork to ascertain whether site conditions are consistent with those described in this report, and that construction conforms to our recommendations. The review of plans and specifications, and construction monitoring and testing by Northeast Engineers & Consultants is an integral part of the conclusions and recommendations made in this report, and if others are retained for these services, the client will be assuming responsibility for any potential claims that may arise during or after construction.




The services described in this report include professional opinions and judgments based on the data collected. Our investigation was performed using the standard of care and level of skill ordinarily exercised under similar circumstances by reputable geotechnical engineers currently practicing in this or similar localities. No other warranty, express or implied, is made as to the conclusions and professional advice included in this report.


We would be pleased to provide you with additional consultation services through the design and construction phases of this challenging project. If you have any questions concerning this report, please contact us.

Respectfully submitted,


NORTHEAST ENGINEERS & CONSULTANTS, INC.



DANIEL P. O'CONNELL, P.E., G.E.  
Chief Geotechnical Engineer



# ALLOWABLE AXIAL CAPACITY (KIPS)




## LEGEND

DOWNWARD  
SF=3  
D+L

UPLIFT  
SF=2  
D+L+W

NORTHEAST ENGINEERS  
& CONSULTANTS, Inc.



CIVIL  
ENVIRONMENTAL  
SURVEYING  
TRANSPORTATION  
STRUCTURAL  
GEOTECHNICAL  
MARINE  
MATERIALS TESTING

42 VALLEY ROAD  
MIDDLETOWN, RHODE ISLAND 02842  
TEL: (401) 849-0810 FAX: (401) 846-4189

NEW MAINTENANCE HANGER  
RHODE ISLAND NATIONAL GUARD  
QUONSET AIR NATIONAL GUARD BASE  
NORTH KINGSTOWN, RHODE ISLAND

THE BENHAM GROUP


DATE: 28MAR01

TIMBER PILES

FIGURE NO.

2 of 4





**LEGEND**

DOWNWARD  
SF=3  
D+L

UPLIFT  
SF=2  
D+L+W

**NORTHEAST ENGINEERS  
& CONSULTANTS, Inc.**



42 VALLEY ROAD  
NORFOLK, RHODE ISLAND 02842  
TEL: (401) 843-0810 FAX: (401) 846-4189

CIVIL  
ENVIRONMENTAL  
SURVEYING  
TRANSPORTATION  
STRUCTURAL  
GEOTECHNICAL  
MARINE  
MATERIALS TESTING

NEW MAINTENANCE HANGER  
RHODE ISLAND NATIONAL GUARD  
QUONSET AIR NATIONAL GUARD BASE  
NORTH KINGSTOWN, RHODE ISLAND

THE BENHAM GROUP


**STEEL PIPE PILES  
(CLOSED END, DRIVEN)**

DATE: 28MAR01

FIGURE NO.

3 of 4

# ALLOWABLE AXIAL CAPACITY (KIPS)




## LEGEND

DOWNWARD  
SF=3  
D+L

UPLIFT  
SF=2  
D+L+W

NORTHEAST ENGINEERS  
& CONSULTANTS, Inc.



42 VALLEY ROAD  
MIDDLETOWN, RHODE ISLAND 02842  
TEL: (401) 849-0610 FAX: (401) 846-4169

CIVIL  
ENVIRONMENTAL  
SURVEYING  
TRANSPORTATION  
STRUCTURAL  
GEOTECHNICAL  
MARINE  
MATERIALS TESTING

NEW MAINTENANCE HANGER  
RHODE ISLAND NATIONAL GUARD  
QUONSET AIR NATIONAL GUARD BASE  
NORTH KINGSTOWN, RHODE ISLAND

DRILLED CAST-IN-PLACE  
CONCRETE PILES

THE BENHAM GROUP

DATE: 28MAR01

FIGURE NO.

4 of 4



## 10.0 APPENDICES



## **APPENDIX A: BORING LOGS AND LAB TEST RESULTS**

---



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **N. E. ENGINEERS****MIDDLETOWN, R.I.**PROJECT **NEW MAINTAINENCE HANGAR****R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>D. BILEZIKIAN</b>	BORING NO.	<b>B-1</b>	CASING		SAMPLER		CORE BARREL	
INSPECTOR		SHEET	<b>1</b>	TYPE	<b>HSA</b>	<b>SS</b>			
LINE & STA	OFFSET	OF	<b>1</b>	SIZE ID	<b>4.25 IN./3.00 IN.</b>	<b>1.375 IN.</b>			
SUR.ELEV.		FILE		HAMMER WT.	<b>300 LB.</b>	<b>140 LB.</b>			
START	<b>JANUARY 25, 2001</b>	NO.	<b>01014</b>	HAMM. FALL	<b>24 IN.</b>	<b>30 IN.</b>			
FINISH	<b>JANUARY 25, 2001</b>								

DEPTH	COL A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0' 6"-2' 6"	17"/24"	5-10	S	Medium		Moist, olive brown FINE TO MEDIUM SAND, trace - little silt, trace organics
					9-11		Dense	0' 6"	
									Dry, tan, FINE TO MEDIUM SAND
10		2	5'-7'	18"/24"	1-2	S	Very	5' 10"	Wet, tan to brown, FINE SAND
					1/12"		Loose		Wet, brown ORGANIC SILT
								6' 10"	
									Wet, olive brown FINE SAND, little silt, trace organics
15		3	10'-12'	16"/24"	33-28	S	Dense		Wet, gray-brown FINE TO COARSE SAND, little fine gravel, trace silt and angular rock fragments (poss. fill)
					11-9				
20		14	15'-17'	16"/24"	4-4	S	Loose	16' 6"	Wet, gray-brown FINE SAND, trace fine to coarse gravel
		21			4-3				Wet, brown MEDIUM SAND, trace coarse sand and fine gravel
		32							NOTE: SWITCHED TO NW CASING AT 18'
		16	18'-20'	16"/24"	12-25	S	Dense		Brown, FINE SAND, little medium sand, trace coarse sand, silt and shell fragments
25		18			16-18				
		23							
		47							
		46							
30		48	23'-25'	18"/24"	28-31	S	Very		Gray, FINE SAND, trace - little silt
		34			33-27		Dense		
		49							
		57							
35		75							
		65	28'-30'	14"/24"	23-28	S	Very		Gray-brown FINE SAND, trace silt
		80			41-49		Dense		
		104							
40		70							
		98							
		103	33'-35'	17"/24"	15-19	S	Dense		Gray, FINE SAND, trace - little silt
		85			17-25				
		98							
		113							
		109							
		9	38'-38'2"	1"/2"	100/2"	S	Spoon	38' 2"	Poor Recovery (rock fragments)
							Refusal		END OF BORING AT 38' 2"

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density Cohesive Consistency  
0-4 Very Loose 0-2 Very Soft  
5-9 Loose 3-4 Soft  
10-29 Med. Dense 5-8 Med. Stiff  
30 - 49 Very Dense 9-15 Stiff  
50+ Very Dense 16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 7 ft. AFTER 0 HRS  
AT        AFTER        HRS  
NOTE: Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **N. E. ENGINEERS****MIDDLETOWN, R.I.**PROJECT **NEW MAINTAINENCE HANGAR****R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>D. BILEZIKIAN</b>	BORING NO.	<b>B-2</b>	CASING	SAMPLER	CORE BARREL
INSPECTOR		SHEET	<b>1</b>	TYPE	<b>HSA</b>	<b>SS</b>
LINE & STA	OFFSET	OF	<b>1</b>	SIZE ID	<b>4.25 IN./3.00 IN.</b>	<b>1.375 IN.</b>
SUR.ELEV.		FILE		HAMMER WT.	<b>300 LB.</b>	<b>140 LB.</b>
START	<b>JANUARY 26, 2001</b>	NO.	<b>01014</b>	HAMM. FALL	<b>24 IN.</b>	<b>30 IN.</b>
FINISH	<b>JANUARY 26, 2001</b>					

DEPTH	COL. A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0'-2'	22"/24"	29-17	S	Dense		Dry, dark brown, silty, FINE TO COARSE SAND, some organics (frost to 10")
					22-17			1' 4"	Light gray, FINE TO COARSE SAND
10		2	5'-7'	12"/24"	3-4	S	Loose		Moist, gray FINE TO MEDIUM SAND, trace coarse sand and fine to medium gravel
					2-2				
15		3	10'-12'	22"/24"	2-2	S	Very Loose	11'	Wet, gray FINE TO MEDIUM SAND
					2-2				Dark brown, fibrous PEAT
20		4	15'-17'	24"/24"	5-10	S	Medium Dense		Gray, FINE TO MEDIUM SAND, trace coarse sand
					14-14				NOTE: Switched to NW casing at 18'
25		3	18'-20'	16"/24"	11-16	S	Dense		Gray FINE SAND, little medium sand
		10			18-22				
30		15	23'-25'	14"/24"	19-22	S	Dense		Gray-brown FINE TO MEDIUM SAND, trace-little coarse sand and fine gravel
		22			25-32				
35		31	28'-30'	18"/24"	15-25	S	Dense	29' 6"	Gray-brown, FINE TO MEDIUM SAND, trace-little coarse sand
		20			23-26				Brown, MEDIUM SAND, trace-little coarse sand and fine gravel
40		35	33'-35'	15"/24"	12-12	S	Medium Dense		Gray, FINE SAND, trace - little silt
		36			11-11				
		9	38'-40"	15"/24"	7-9	S	Medium Dense		Gray, FINE SAND, little - some silt
					7-9			40'	END OF BORING AT 40'

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density Cohesive Consistency  
0-4 Very Loose 0-2 Very Soft  
5-9 Loose 3-4 Soft  
10-29 Med. Dense 5-8 Med. Stiff  
30 - 49 Very Dense 9-15 Stiff  
50+ Very Dense 16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 9 ft. AFTER 0 HRS  
AT        AFTER        HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>D. BILEZIKIAN</b>	BORING NO.	<b>B-3</b>	CASING		SAMPLER		CORE BARREL	
INSPECTOR		SHEET	<b>1</b>	TYPE	<b>HSA</b>		<b>SS</b>		
LINE & STA	OFFSET	OF	<b>2</b>	SIZE ID	<b>4.25 IN.</b>		<b>1.375 IN.</b>		
SUR.ELEV.		FILE		HAMMER WT.			<b>140 LB.</b>		
START	<b>JANUARY 25, 2001</b>	NO.	<b>01014</b>	HAMM. FALL			<b>30 IN.</b>		
FINISH	<b>JANUARY 26, 2001</b>								

DEPTH	COL. A	NO.	DEPTH RANGE FEET	SAMPLE REC 7 PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0'6"-2'6"	14"/24"	11-15	S	Medium	1' 6"	Dry, brown FINE TO COARSE SAND, trace fine gravel (FILL)
					13-14		Dense		Dry, tan FINE SAND, little medium to coarse sand (FILL)
10		2	5'-7'	13"/24"	5-4	S	Loose		Wet, tan, FINE TO MEDIUM SAND
					4-4				
15		3	10'-12'	12"/24"	3-2	S	Very		Wet, light brown, FINE SAND, trace silt, trace coarse gravel
					2-4		Loose		
20		4	15'-17'	20"/24"	10-15	S	Medium		Wet, gray-brown FINE SAND, trace medium to coarse sand trace-little silt
					12-14		Dense		NOTE: SWITCHED TO NW CASING AT 18'
		5	18'-20'	0"/24"	12-15	S	Dense		No Recovery (gray fine sand in wash)
					15-18				
25		6	23'-25'	16"/24"	8-9	S	Medium		Dark gray, FINE SAND, little-some silt
					14-23		Dense		
30		7	28'-30'	7"/24"	14-12	S	Medium		Dark gray, SILT, little fine sand
					11-12		Dense		
35		8	33'-35'	14"/24"	15-25	S	Very		Gray, FINE SAND, trace silt
					25-29		Dense		
40		9	38'-40'	18"/24"	18-22	S	Very		Gray-brown, FINE SAND, some silt
					29-32		Dense	40'	END OF BORING AT 40'

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft AFTER 0 HRS  
AT        AFTER        HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER		C. SETTE				BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR		M. PONTE				NO. B-4							
LINE & STA		OFFSET				SHEET 1		TYPE		HSA/NW		SS	
SUR.ELEV.						OF 2		SIZE ID		4.25 IN./3.00 IN.		1.375 IN.	
START		FEBRUARY 1, 2001				FILE		HAMMER WT.		300 LB.		140 LB.	
FINISH		FEBRUARY 1, 2001				NO. 01014		HAMM. FALL		24 IN.		30 IN.	
DEPTH	COL A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS				
5		1	0'-2'	7"/24"	31-9	S	Medium		Moist, dark brown silty FINE SAND, some medium to coarse gravel, little-some organics (FILL)				
					3-3		Dense						
10		2	5'-7'	9"/24"	5-9	S	Medium	5'-7'	Wet, olive-gray FINE SAND, little medium to coarse sand (FILL)				
					13-12		Dense						
15		3	10'-12'	22"/24"	2-2	S	Very	10'-12'	Moist, greenish-gray FINE SAND AND SILT, some organics (FILL)				
					2-4		Loose						
20		4	15'-17'	14"/24"	5-5	S	Medium	15'-17'	Wet, greenish-gray FINE SAND, little silt NOTE: Switched to NW casing at 18'				
					5-5		Dense						
25		5	18'-20'	17"/24"	11-11	S	Medium	18'-20'	Wet, greenish-gray FINE SAND, little silt				
					14-18		Dense						
30		6	23'-25'	8"/24"	10-11	S	Medium	23'-25'	Wet, greenish-gray FINE SAND, little silt, trace coarse sand				
					11-11		Dense						
35		7	28'-30'	14"/24"	9-8	S	Medium	28'-30'	Wet, greenish-gray FINE TO MEDIUM SAND, trace coarse sand				
					9-11		Dense						
40		8	33'-35'	16"/24"	5-6	S	Medium	33'-35'	Wet, greenish-gray FINE TO MEDIUM SAND, trace-little coarse sand				
					11-11		Dense						
40		9	38'-40'	9"/24"	11-20	S	Dense	38'-40'	Wet, brown FINE TO MEDIUM SAND, little coarse sand and fine to medium gravel				
					23-22								

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A****PROPORTIONS USED**trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft. AFTER 0 HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.





**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

**125 Tremont Street  
Rehoboth, MA 02769**

# BORING / WELL LOG

**CLIENT NORTHEAST ENGINEERS**

**MIDDLETOWN R.I.**

**PROJECT R.I. AIR NATIONAL GUARD**

**QUONSET POINT, R.I.**

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	FEBRUARY 1, 2001
FINISH	FEBRUARY 1, 2001

BORING	
NO.	B-5
SHEET	1
OF	1
FILE	
NO.	01014

	CASING	SAMPLER	CORE BARREL
TYPE	<u>HSA</u>	<u>SS</u>	
SIZE ID	<u>4.25 IN.</u>	<u>1.375 IN.</u>	
HAMMER WT.	<u></u>	<u>140 LB.</u>	
HAMM. FALL		<u>30 IN.</u>	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

**PROPORTIONS USED**

trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%

## GROUNDWATER OBSERVATIONS

AT 6 ft. AFTER 0 HRS  
AT AFTER HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS**  
**MIDDLETOWN R.I.**  
PROJECT **R.I. AIR NATIONAL GUARD**  
**QUONSET POINT, R.I.**

DRILLER		C. SETTE				BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR		M. PONTE				NO.		B-6					
LINE & STA		OFFSET				SHEET		1		TYPE		HSA/NW SS	
SUR.ELEV.						OF		2		SIZE ID		4.25 IN./3.00 IN. 1.375 IN.	
START		FEBRUARY 2, 2001				FILE				HAMMER WT.		300 LB. 140 LB.	
FINISH		FEBRUARY 2, 2001				NO.		01014		HAMM. FALL		24 IN. 30 IN.	
DEPTH	COL. A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS				
5		1	0'-2'	14"/24"	5-11	S	Medium		Dry, dark-brown, silty FINE TO MEDIUM SAND, trace corase sand and organics (FILL)				
					10-8		Dense						
	10		2	5'-7'	13"/24"	6-14	S	Dense		Dry brown, FINE TO COARSE SAND			
					18-15								
15			3	10'-12'	7"/24"	8-12	S	Dense		Wet, olive brown, FINE TO COARSE SAND			
					20-27								
	20		4	15'-17'	20"/24"	11-5	S	Medium		Greenish-gray FINE TO MEDIUM SAND NOTE: Switched to NW casing at 18'			
					7-17		Dense						
25			5	18'-20'	18"/24"	15-15	S	Dense		Greenish-gray FINE SAND, little-some silt			
					20-21								
	30		6	23'-25'	7"/24"	18-20	S	Dense		Greenish-gray FINE SAND, little-some silt			
					20-19								
35			7	28'-30'	9"/24"	7-9	S	Medium		Greenish-gray FINE SAND, little silt			
					11-13		Dense						
	40		8	33'-35'	14"/24"	22-23	S	Dense		Gray-brown FINE SAND AND SILT			
					25-39								
40			9	38'-40'	13"/24"	15-24	S	Very		Greenish-gray FINE SAND, little-some silt			
					30-36		Dense						

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 7 ft. AFTER 0 HRS  
AT        AFTER        HRS

NOTE: Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

**CLIENT NORTHEAST ENGINEERS**

**MIDDLETOWN R.I.**

PROJECT R.I. AIR NATIONAL GUARD

QUONSET POINT, R.I.

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	FEBRUARY 2, 2001
FINISH	FEBRUARY 2, 2001

BORING	
NO.	B-6
SHEET	2
OF	2
FILE	
NO.	01014

	CASING	SAMPLER	CORE BARREL
TYPE	<u>HSA/NW</u>	<u>SS</u>	
SIZE ID	<u>4.25 IN./3.00 IN.</u>	<u>1.375 IN.</u>	
HAMMER WT.	<u>300 LB.</u>	<u>140 LB.</u>	
HAMM. FALL	<u>24 IN.</u>	<u>30 IN.</u>	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

## PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER		C. SETTE				BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR		M. PONTE				NO. B-7							
LINE & STA		OFFSET				SHEET 1		TYPE		HSA/NW		SS	
SUR.ELEV.						OF 2		SIZE ID		4.25 IN./3.00 IN.		1.375 IN.	
START		FEBRUARY 2, 2001				FILE		HAMMER WT.		300 LB.		140 LB.	
FINISH		FEBRUARY 5, 2001				NO. 01014		HAMM. FALL		24 IN.		30 IN.	
DEPTH	COL A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS				
5		1	0'-2'	14"/24"	8-8	S	Medium		Dry, greenish-brown FINE TO MEDIUM SAND, trace fine to medium gravel and bituminous concrete (FILL)				
					20-22		Dense						
									Wet, greenish-gray FINE TO MEDIUM SAND, trace coarse sand (FILL)				
		2	5'-7'	11"/24"	5-9	S	Medium						
					9-8		Dense						
10									Dry, dark brown PEAT				
		3	10'-12'	24"/24"	1-1	S	Very						
					1-5		Loose		Wet, greenish-gray FINE TO MEDIUM SAND, little - some silt NOTE: Switched to NW casing at 18'				
15									Wet, greenish-gray FINE TO MEDIUM SAND, little - some silt				
		4	15'-17'	24"/24"	2-2	S	Very						
					2-5		Loose		Wet, greenish-gray FINE SAND, some silt				
20									Wet, greenish-gray FINE TO MEDIUM SAND, little-some silt				
		5	18'-20'	10"/24"	10-10	S	Medium						
					11-13		Dense		Wet, greenish-gray FINE TO MEDIUM SAND, little-some silt				
25									Wet, greenish-gray FINE TO MEDIUM SAND, little-some silt				
		6	23'-25'	11"/24"	10-10	S	Medium						
					9-8		Dense		Wet, greenish-gray FINE SAND, some silt				
30									Wet, greenish-gray FINE SAND, some silt				
		7	28'-30'	13"/24"	8-7	S	Medium						
					18-26		Dense		Wet, olive-brown FINE SAND, some silt				
35									Wet, olive-brown FINE SAND, some silt				
		8	33'-35'	12"/24"	6-8	S	Medium						
					10-11		Dense		Wet, olive-brown FINE SAND, some silt				
40									Wet, olive-brown FINE SAND, some silt				
		9	38'-40'	2"/24"	20-20	S	Very						
					33-20		Dense						

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft. AFTER 0 HRS  
AT AFTER HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

**ENVIRO-TECH  
DRILLING, INC.**

125 Tremont Street  
Rehoboth, MA 02769

**BORING /  
WELL  
LOG**

**CLIENT NORTHEAST ENGINEERS**

**MIDDLETOWN R.I.**

**PROJECT R.I. AIR NATIONAL GUARD**

**QUONSET POINT, R.I.**

DRILLER	C. SETTE	BORING		CASING	SAMPLER	CORE BARREL
INSPECTOR	M. PONTE	NO.	B-7			
LINE & STA	_____ OFFSET _____	SHEET	2	TYPE	HSA/NW	SS
SUR. ELEV.		OF	2	SIZE ID	4.25 IN./3.00 IN.	1.375 IN.
START	FEBRUARY 2, 2001	FILE		HAMMER WT.	300 LB.	140 LB.
FINISH	FEBRUARY 5, 2001	NO.	01014	HAMM. FALL	24 IN.	30 IN.

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

Soilless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT	<u>6 FT.</u>	AFTER	<u>0</u>	HRS
AT		AFTER		HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>C. SETTE</b>	BORING		CASING		SAMPLER		CORE BARREL
INSPECTOR	<b>M. PONTE</b>	NO.	<b>B-8</b>					
LINE & STA	_____ OFFSET _____	SHEET	<b>1</b>	TYPE	<b>HSA/NW</b>	<b>SS</b>		
SUR.ELEV.		OF	<b>2</b>	SIZE ID	<b>4.25 IN./3.00 IN.</b>	<b>1.375 IN.</b>		
START	<b>FEBRUARY 5, 2001</b>	FILE		HAMMER WT.	<b>300 LB.</b>	<b>140 LB.</b>		
FINISH	<b>FEBRUARY 6, 2001</b>	NO.	<b>01014</b>	HAMM. FALL	<b>24 IN.</b>	<b>30 IN.</b>		

DEPTH	COL A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0'-2'	13"/24"	6-12	S	Medium		Dry, brown, silty FINE TO COARSE SAND, little fine to medium gravel (FILL)
					6-6		Dense		
10		2	5'-7'	17"/24"	4-5	S	Loose		Wet, greenish-brown FINE SAND AND SILT (FILL)
					3-4				
15		3	10'-12'	20"/24"	1-2	S	Loose		Moist, dark-brown PEAT
					3-4				
20		4	15'-17'	9"/24"	3-3	S	Loose		Wet, olive-brown FINE SAND, some silt NOTE: Switched to NW casing at 18'
					5-4				
25		5	18'-20'	20"/24"	8-10	S	Medium		Wet, greenish-gray FINE SAND, little silt
					10-18		Dense		
30		6	23'-25'	7"/24"	17-17	S	Dense		Wet, olive-brown FINE SAND, little-some coarse sand and fine to medium gravel, trace-little silt
					20-25				
35		7	28'-30'	8"/24"	6-10	S	Medium		Wet, olive-brown FINE TO COARSE SAND, trace-little fine gravel, trace silt
					9-11		Dense		
40		8	33'-35'	8"/24"	10-9	S	Medium		Wet, greenish-gray FINE SAND, some silt
					7-10		Dense		
40		9	38'-40'	11"/24"	9-24	S	Very		Wet, gray FINE TO COARSE SAND, some silt, trace-little fine gravel
					58-120		Dense		

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft. AFTER 0 HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

**ENVIRO-TECH  
DRILLING, INC.**

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

**CLIENT NORTHEAST ENGINEERS**

**MIDDLETOWN R.I.**

PROJECT R.I. AIR NATIONAL GUARD

QUONSET POINT, R.I.

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	<b>FEBRUARY 5, 2001</b>
FINISH	<b>FEBRUARY 6, 2001</b>

BORING	
NO.	<b>B-8</b>
SHEET	<b>2</b>
OF	<b>2</b>
FILE	
NO.	<b>01014</b>

	CASING	SAMPLER	CORE BARREL
TYPE	HSA/NW	SS	
SIZE ID	4.25 IN./3.00 IN.	1.375 IN.	
HAMMER WT.	300 LB.	140 LB.	
HAMM. FALL	24 IN.	30 IN.	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.





Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER		C. SETTE				BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR		M. PONTE				NO.		B-9					
LINE & STA		_____ OFFSET _____				SHEET		1		TYPE		HSA/NW SS	
SUR.ELEV.						OF		2		SIZE ID		4.25 IN./300 IN. 1.375 IN.	
START		FEBRUARY 12, 2001				FILE				HAMMER WT.		300 LB. 140 LB.	
FINISH		FEBRUARY 16, 2001				NO.		01014		HAMM. FALL		24 IN. 30 IN.	
DEPTH	COL. A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS				
5		1	0'-2'	16"/24"	4-8	S	Medium		Dry, tan, FINE SAND, trace silt				
					8-13		Dense						
10		2	5'-7'	13"/24"	1-1	S	Very		Wet, greenish-gray FINE SAND, some silt, trace coarse sand				
					2-5		Loose						
15		3	10'-12'	18"/24"	1-2	S	Loose		Moist, dark brown PEAT				
					3-2								
20		4	15'-17'	9"/24"	4-5	S	Medium		Wet, greenish-gray FINE TO MEDIUM SAND, some silt NOTE: Switched to NW casing at 18'				
					8-6		Dense						
25		5	18'-20'	16"/24"	2-3	S	Loose		Wet, gray-brown SILT, possible organics				
					5-9								
30		6	23'-25'	10"/24"	6-7	S	Medium		Wet, gray-brown FINE SAND AND SILT, trace medium-sand				
					7-8		Dense						
35		7	28'-30'	9"/24"	5-7	S	Medium		Wet, gray-brown FINE SAND, little-some silt, trace coarse sand				
					12-12		Dense						
40		8	33'-35'	14"/24"	5-14	S	Medium		Wet, gray, FINE TO COARSE SAND AND GRAVEL				
					11-11		Dense						
40		9	38'-40'	14"/24"	6-16	S	Medium		Wet, gray-brown FINE TO COARSE SAND, little fine gravel, little silt				
					8-4		Dense						

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density Cohesive Consistency  
0-4 Very Loose 0-2 Very Soft  
5-9 Loose 3-4 Soft  
10-29 Med. Dense 5-8 Med. Stiff  
30 - 49 Very Dense 9-15 Stiff  
50+ Very Dense 16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft AFTER 0 HRS  
AT AFTER HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

**CLIENT NORTHEAST ENGINEERS**

**MIDDLETOWN R.I.**

PROJECT R.I. AIR NATIONAL GUARD

## QUONSET POINT, R.I.

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	<b>FEBRUARY 12, 2001</b>
FINISH	<b>FEBRUARY 16, 2001</b>

BORING	
NO.	<b>B-9</b>
SHEET	<b>2</b>
OF	<b>2</b>
FILE	
NO.	<b>01014</b>

	CASING	SAMPLER	CORE BARREL
TYPE	<u>HSA/NW</u>	<u>SS</u>	
SIZE ID	<u>4.25 IN./3.00 IN.</u>	<u>1.375 IN.</u>	
HAMMER WT.	<u>300 LB.</u>	<u>140 LB.</u>	
HAMM. FALL	<u>24 IN.</u>	<u>30 IN.</u>	

DEPTH	COL A	SAMPLE				MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET
		NO.	DEPTH RANGE FEET	REC / PEN	BLOWS/6" ON SAMPLER		

**SAMPLE CLASSIFICATION  
AND REMARKS**

Wet, gray, SILT, little fine sand

Wet, gray, SILT  
END OF BORING AT 50'

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

## PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Nonless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT 6 ft. AFTER 0 HRS  
AT AFTER HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>C. SETTE</b>	BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR	<b>M. PONTE</b>	NO.	<b>B-10</b>						
LINE & STA	_____ OFFSET _____	SHEET	<b>1</b>	TYPE	<b>HSA</b>	<b>SS</b>			
SUR.ELEV.		OF	<b>2</b>	SIZE ID	<b>4.25 IN.</b>	<b>1.375 IN.</b>			
START	<b>FEBRUARY 16, 2001</b>	FILE		HAMMER WT.		<b>140 LB.</b>			
FINISH	<b>FEBRUARY 16, 2001</b>	NO.	<b>01014</b>	HAMM. FALL		<b>30 IN.</b>			

DEPTH	COL. A	NO.	DEPTH RANGE FEET	SAMPLE REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0'-2'	22"/24"	6-12	S	Medium		Dry, tan to brown FINE TO MEDIUM SAND, trace coarse sand (FILL)
					14-16		Dense		
10		2	5'-7'	20"/24"	2-3	S	Loose		Wet, brown, FINE SAND, little to some silt (FILL)
					2-2				
15		3	10'-12'	20"/24"	3-5	S	Medium		Wet, dark brown, FINE SAND, trace silt, organics, roots (FILL)
					9-6		Dense		
20		4	15'-17'	9"/24"	6-7	S	Medium		Wet, brown, FINE TO MEDIUM SAND, little coarse sand and fine gravel
					10-16		Dense		
25		5	20'-22'	24"/24"	15-16	S	Dense		Wet, brown FINE TO COARSE SAND, little - some fine gravel
					30-35				
30		6	25'-27'	8"/24"	10-9	S	Dense		Wet, gray SILT AND FINE SAND
					10-13				
35		7	30'-32'	11"/24"	9-10	S	Medium		Wet, light brown FINE SAND, little-some silt
					18-30		Dense		
40		8	35'-37'	18"/24"	14-25	S	Very		Wet, gray, FINE SAND, some silt
					29-42		Dense		

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft AFTER 0 HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

**CLIENT NORTHEAST ENGINEERS**

## MIDDLETOWN R.I.

**PROJECT R.I. AIR NATIONAL GUARD**

**QUONSET POINT, R.I.**

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	FEBRUARY 16, 2001
FINISH	FEBRUARY 16, 2001

BORING	
NO.	B-10
SHEET	2
OF	2
FILE	
NO.	01014

	CASING	SAMPLER	CORE BARREL
TYPE	HSA	SS	
SIZE ID	4.25 IN.	1.375 IN.	
HAMMER WT.		140 LB.	
HAMM. FALL		30 IN.	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

## PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Slonless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

**PROPORTIONS USED**  
 trace 0-10%  
 little 10-20%  
 some 20-35%  
 and 35-50%

## GROUNDWATER OBSERVATIONS

AT 6 ft. AFTER 0 HRS  
AT AFTER HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

CLIENT NORTHEAST ENGINEERS

**MIDDLETOWN R.I.**

PROJECT R.I. AIR NATIONAL GUARD

**QUONSET POINT, R.I.**

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	FEBRUARY 12, 2001
FINISH	FEBRUARY 12, 2001

BORING	
NO.	B-11
SHEET	1
OF	1
FILE	
NO.	01014

	CASING	SAMPLER	CORE BARREL
TYPE	<u>HSA</u>	<u>SS</u>	
SIZE ID	<u>4.25 IN.</u>	<u>1.375 IN.</u>	
HAMMER WT.	<u></u>	<u>140 LB.</u>	
HAMM. FALL	<u></u>	<u>30 IN.</u>	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT	<u>6 ft.</u>	AFTER	<u>0</u>	HRS
AT		AFTER		HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

**ENVIRO-TECH  
DRILLING, INC.**

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

## CLIENT NORTHEAST ENGINEERS

## MIDDLETOWN R.I.

PROJECT R.I. AIR NATIONAL GUARD  
QUONSET POINT, R.I.

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	FEBRUARY 12, 2001
FINISH	FEBRUARY 12, 2001

BORING	
NO.	<b>B-12</b>
SHEET	<b>1</b>
OF	<b>1</b>
FILE	
NO.	<b>01014</b>

	CASING	SAMPLER	CORE BARREL
TYPE	<u>HSA</u>	<u>SS</u>	
SIZE ID	<u>4.25 IN.</u>	<u>1.375 IN.</u>	
HAMMER WT.	<u></u>	<u>140 LB.</u>	
HAMM. FALL		<u>30 IN.</u>	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

**PROPORTIONS USED**  
 trace 0-10%  
 little 10-20%  
 some 20-35%  
 and 35-50%

## GROUNDWATER OBSERVATIONS

AT	<u>6 ft.</u>	AFTER	<u>0</u>	HRS
AT		AFTER		HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER <b>C. SETTE</b>		BORING NO. <b>B-13</b>		CASING		SAMPLER		CORE BARREL	
INSPECTOR <b>M. PONTE</b>		SHEET <b>1</b>		TYPE <b>HSA</b>		SS			
LINE & STA _____ OFFSET _____		OF <b>1</b>		SIZE ID <b>4.25 IN.</b>		<b>1.375 IN.</b>			
SUR.ELEV. _____		FILE _____		HAMMER WT. _____		<b>140 LB.</b>			
START <b>FEBRUARY 12, 2001</b>		NO. <b>01014</b>		HAMM. FALL _____		<b>30 IN.</b>			
FINISH <b>FEBRUARY 12, 2001</b>									
DEPTH	COL A	NO.	DEPTH RANGE FEET	SAMPLE REC 7 PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0-2	13"/24"	8-12	S	Medium		Dry, brown, FINE TO MEDIUM SAND, trace coarse sand and silt
					15-23		Dense		
10		2	5-7	11"/24"	3-4	S	Medium		Wet, gray-brown FINE SAND, trace silt and coarse sand
					6-6		Dense		
15		3	10-12	24"/24"	2-3	S	Loose		Moist, dark brown PEAT, some fine sand
					4-4				
20		4	15-17	16"/24"	6-9	S	Medium		Wet, gray-brown FINE SAND, some silt
					12-13		Dense	17'	
									END OF BORING AT 17'

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 6 ft. AFTER 0 HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

**Tel. (800) 535-3577**

**ENVIRO-TECH  
DRILLING, INC.**

**125 Tremont Street  
Rehoboth, MA 02769**

# BORING / WELL LOG

CLIENT NORTHEAST ENGINEERS

## MIDDLETOWN R.I.

PROJECT R.I. AIR NATIONAL GUARD

**QUONSET POINT, R.I.**

DRILLER	C. SETTE
INSPECTOR	M. PONTE
LINE & STA	_____ OFFSET _____
SUR.ELEV.	_____
START	_____
FINISH	_____

BORING	
NO.	<b>B-14</b>
SHEET	<b>1</b>
OF	<b>1</b>
FILE	
NO.	<b>01014</b>

	CASING	SAMPLER	CORE BARREL
TYPE	HSA	SS	
SIZE ID	4.25 IN.	1.375 IN.	
HAMMER WT.		140 LB.	
HAMM. FALL		30 IN.	

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

## PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Cohesionless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT	<u>6 ft.</u>	AFTER	<u>0</u>	HRS
AT		AFTER		HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



**Tel. (800) 535-3577**

# ENVIRO-TECH DRILLING, INC.

125 Tremont Street  
Rehoboth, MA 02769

# BORING / WELL LOG

CLIENT NORTHEAST ENGINEERS

**MIDDLETOWN R.I.**

PROJECT R.I. AIR NATIONAL GUARD

**QUONSET POINT, R.I.**

DRILLER	C. SETTE	BORING		CASING	SAMPLER	CORE BARREL
INSPECTOR	M. PONTE	NO.	B-15			
LINE & STA	_____ OFFSET _____	SHEET	1	TYPE	HSA	SS
SUR. ELEV.		OF	1	SIZE ID	4.25 IN.	1.375 IN.
START	FEBRUARY 12, 2001	FILE		HAMMER WT.		140 LB.
FINISH	FEBRUARY 12, 2001	NO.	01014	HAMM. FALL		30 IN.

[illegible]

### SAMPLE IDENTIFICATION

S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE

### PENETRATION RESISTANCE

140 lb. Wt. falling 30" on 2" O.D. Sampler	
Nonless Density	Cohesive Consistency
0-4 Very Loose	0-2 Very Soft
5-9 Loose	3-4 Soft
10-29 Med. Dense	5-8 Med. Stiff
30 - 49 Very Dense	9-15 Stiff
50+ Very Dense	16-30 Very Stiff
	31+ Hard

**COLUMN A**

PROPORTIONS USED	
trace	0-10%
little	10-20%
some	20-35%
and	35-50%

## GROUNDWATER OBSERVATIONS

AT 7 ft. AFTER 0 HRS  
AT AFTER HRS

**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.



Tel. (800) 535-3577

**ENVIRO-TECH  
DRILLING, INC.**125 Tremont Street  
Rehoboth, MA 02769**BORING /  
WELL  
LOG**CLIENT **NORTHEAST ENGINEERS****MIDDLETOWN R.I.**PROJECT **R.I. AIR NATIONAL GUARD****QUONSET POINT, R.I.**

DRILLER	<b>C. SETTE</b>	BORING		CASING		SAMPLER		CORE BARREL	
INSPECTOR	<b>M. PONTE</b>	NO.	<b>B-16</b>						
LINE & STA	_____ OFFSET _____	SHEET	<b>1</b>	TYPE	<b>HSA</b>	<b>SS</b>			
SUR.ELEV.		OF	<b>1</b>	SIZE ID	<b>4.25 IN.</b>	<b>1.375 IN.</b>			
START	<b>FEBRUARY 12, 2001</b>	FILE		HAMMER WT.	<b>300 LB.</b>	<b>140 LB.</b>			
FINISH	<b>FEBRUARY 12, 2001</b>	NO.	<b>01014</b>	HAMM. FALL	<b>24 IN.</b>	<b>30 IN.</b>			

DEPTH	COL. A	NO.	DEPTH RANGE FEET	REC / PEN	BLOWS/6" ON SAMPLER	TYPE	MOISTURE DENSITY OR CONSIST	STRAT. CHANGE FEET	SAMPLE CLASSIFICATION AND REMARKS
5		1	0-2	4"/24"	9-24	S	Very		Dry, olive brown, FINE TO MEDIUM SAND, little-some coarse sand and fine to medium gravel (FILL)
					26-24		Dense		
10		2	5-7	8"/24"	8-6	S	Medium		Dry, tan, FINE TO MEDIUM SAND, trace coarse sand
					5-7		Dense		
15		3	10-12	20"/24"	3-4	S	Loose		Wet, tan, FINE SAND, little silt
					3-3				
20		4	15-17	6"/24"	1-1	S	Very		Wet, tan, FINE SAND, little silt
					1-2		Loose	17'	
									END OF BORING AT 17'

**SAMPLE IDENTIFICATION**S - SPLIT SPOON  
T - THIN WALL TUBE  
U - UNDISTURBED PISTON  
O - OPEN END ROD  
W - WASH SAMPLE  
A - AUGER SAMPLE**PENETRATION RESISTANCE**140 lb. Wt. falling 30" on 2" O.D. Sampler  
Cohesionless Density      Cohesive Consistency  
0-4 Very Loose      0-2 Very Soft  
5-9 Loose      3-4 Soft  
10-29 Med. Dense      5-8 Med. Stiff  
30 - 49 Very Dense      9-15 Stiff  
50+ Very Dense      16-30 Very Stiff  
31+ Hard**COLUMN A**PROPORTIONS USED  
trace 0-10%  
little 10-20%  
some 20-35%  
and 35-50%**GROUNDWATER OBSERVATIONS**AT 7 ft. AFTER 0 HRS  
AT \_\_\_\_\_ AFTER \_\_\_\_\_ HRS**NOTE:** Levels may vary with seasonal fluctuation and the degree of soil saturation when the boring was taken.

# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 1/25/01

Date Tested: 2/28/01

Boring #: B1-S1

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine to med sand

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 247.1


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	247.10	100.00%	0.00%
1-1/2"	37.50	0.00	247.10	100.00%	0.00%
3/4"	19.00	0.00	247.10	100.00%	0.00%
1/2"	12.50	0.00	247.10	100.00%	0.00%
3/8"	9.50	0.00	247.10	100.00%	0.00%
#4	4.75	6.10	241.00	97.53%	2.47%
#10	2.00	12.20	228.80	92.59%	7.41%
PAN	0.00	228.80			
TOTAL:		247.10		Loss during testing:	0.00%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 228.8

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	79.20	149.10	65.17%	60.34%	39.66%
#50	0.3	46.40	102.70	44.89%	41.56%	58.44%
#100	0.15	64.10	38.60	16.87%	15.62%	84.38%
#200	0.075	25.00	13.60	5.94%	5.50%	94.50%
PAN	0	13.60				
TOTAL:		228.30		Loss during testing:	0.22%	

### GRADATION CURVE



# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 1/25/01

Date Tested: 2/28/01

Boring #: B1- S4

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine sand, little silt

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 289.9


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	289.90	100.00%	0.00%
1-1/2"	37.50	0.00	289.90	100.00%	0.00%
3/4"	19.00	16.90	273.00	94.17%	5.83%
1/2"	12.50	3.60	269.40	92.93%	7.07%
3/8"	9.50	14.10	255.30	88.06%	11.94%
#4	4.75	9.90	245.40	84.65%	15.35%
#10	2.00	29.20	216.20	74.58%	25.42%
PAN	0.00	217.50			
TOTAL:		291.20		Loss during testing:	-0.45%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 217.5

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	126.50	91.00	41.84%	31.39%	68.61%
#50	0.3	18.70	72.30	33.24%	24.94%	75.06%
#100	0.15	31.00	41.30	18.99%	14.25%	85.75%
#200	0.075	18.10	23.20	10.67%	8.00%	92.00%
PAN	0	23.20				
TOTAL:		217.50		Loss during testing:	0.00%	

### GRADATION CURVE



# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 1/25/01

Date Tested: 2/28/01

Boring #: B1- S7

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine sand, trace silt

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 215.4


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	215.40	100.00%	0.00%
1-1/2"	37.50	0.00	215.40	100.00%	0.00%
3/4"	19.00	0.00	215.40	100.00%	0.00%
1/2"	12.50	0.00	215.40	100.00%	0.00%
3/8"	9.50	0.00	215.40	100.00%	0.00%
#4	4.75	0.20	215.20	99.91%	0.09%
#10	2.00	0.20	215.00	99.81%	0.19%
PAN	0.00	215.00			
TOTAL:		215.40		Loss during testing:	0.00%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 215.0

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	2.10	213.30	99.21%	99.03%	0.97%
#50	0.3	4.00	209.30	97.35%	97.17%	2.83%
#100	0.15	51.00	158.30	73.63%	73.49%	26.51%
#200	0.075	99.70	58.60	27.26%	27.21%	72.79%
PAN	0	58.60				
TOTAL:		215.40		Loss during testing:	-0.19%	

### GRADATION CURVE



# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 2/2/01

Date Tested: 2/28/01

Boring #: B6-S2

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine to coarse sand

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 280.2


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	280.20	100.00%	0.00%
1-1/2"	37.50	0.00	280.20	100.00%	0.00%
3/4"	19.00	0.00	280.20	100.00%	0.00%
1/2"	12.50	17.30	262.90	93.83%	6.17%
3/8"	9.50	0.00	262.90	93.83%	6.17%
#4	4.75	23.20	239.70	85.55%	14.45%
#10	2.00	59.20	180.50	64.42%	35.58%
PAN	0.00	180.50			
TOTAL:		280.20	Loss during testing:		0.00%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 180.5

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	131.40	49.10	27.20%	17.52%	82.48%
#50	0.3	14.80	34.30	19.00%	12.24%	87.76%
#100	0.15	13.60	20.70	11.47%	7.39%	92.61%
#200	0.075	8.60	12.10	6.70%	4.32%	95.68%
PAN	0	12.10				
TOTAL:		180.50	Loss during testing:		0.00%	

### GRADATION CURVE



# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 2/2/01

Date Tested: 2/28/01

Boring #: B7- S8

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine sand, some silt

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 293.4


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	293.40	100.00%	0.00%
1-1/2"	37.50	0.00	293.40	100.00%	0.00%
3/4"	19.00	0.00	293.40	100.00%	0.00%
1/2"	12.50	0.00	293.40	100.00%	0.00%
3/8"	9.50	0.00	293.40	100.00%	0.00%
#4	4.75	0.00	293.40	100.00%	0.00%
#10	2.00	1.20	292.20	99.59%	0.41%
PAN	0.00	292.20			
TOTAL:		293.40		Loss during testing:	0.00%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 292.2

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	35.70	256.30	87.71%	87.36%	12.64%
#50	0.3	49.70	206.60	70.70%	70.42%	29.58%
#100	0.15	136.20	70.40	24.09%	23.99%	76.01%
#200	0.075	56.20	14.20	4.86%	4.84%	95.16%
PAN	0	14.20				
TOTAL:		292.00		Loss during testing:	0.07%	

GRADATION CURVE



# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled: 2/16/01

Date Tested: 2/28/01

Boring #: B9-S6

Test #: 1

Calculated By: MDP

Checked By:

## PARTICLE-SIZE ANALYSIS: ASTM D-422

Description of soil: fine sand and silt

Location: Hanger

### Part A: COARSE SIEVE ANALYSIS

Weight of oven dry sample: 250.1


Sieve	Sieve Open. (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent pass. of whole samp.	Percent ret. of whole samp.
3"	75.00	0	250.10	100.00%	0.00%
1-1/2"	37.50	0.00	250.10	100.00%	0.00%
3/4"	19.00	0.00	250.10	100.00%	0.00%
1/2"	12.50	0.00	250.10	100.00%	0.00%
3/8"	9.50	0.00	250.10	100.00%	0.00%
#4	4.75	2.50	247.60	99.00%	1.00%
#10	2.00	3.10	244.50	97.76%	2.24%
PAN	0.00	245.00			
TOTAL:		250.60	Loss during testing:		-0.20%

### Part B: FINE SIEVE ANALYSIS

Weight of oven dry sample: 245.0

Sieve	Sieve Opening (mm)	Grams Ret. (g)	Grams Pass. (g)	Percent Pass. of fine samp.	Percent Pass. of whole samp.	Percent Ret. of whole samp.
#40	0.425	26.10	218.40	89.14%	87.33%	12.67%
#50	0.3	18.60	199.80	81.55%	79.89%	20.11%
#100	0.15	72.80	127.00	51.84%	50.78%	49.22%
#200	0.075	72.50	54.50	22.24%	21.79%	78.21%
PAN	0	54.50				
TOTAL:		244.50	Loss during testing:		0.20%	

### GRADATION CURVE





# NORTHEAST ENGINEERS & CONSULTANTS, Inc.

42 VALLEY ROAD, MIDDLETOWN, RHODE ISLAND 02842 PH.: (401) 849 - 0810 FAX: (401) 846 - 4169

Project: RI Air National Guard

Project Number: 01005.0

Date Sampled:

Date Tested:

Sample #: B 13, 0 to 3 feet

Test #: 1

Calculated By: MDP

Checked By:

## MODIFIED PROCTOR COMPACTION - ASTM D-1557

Description of soil: Dark gray silty sand w / gravel

Date Sampled:

Location: Proposed parking lot

Number of Layers: 5

Weight of Hammer: 10 lbf

No. of Blows per Layer: 25


Procedure: A

Test #	Weight of Mold, W1 (g)	Weight of mold & moist soil (g)	Weight of moist soil (g)	Moist unit weight, (lb/ft <sup>3</sup> )	Moisture Content, (%)	Dry Unit Weight, (lb/ft <sup>3</sup> )
1	4,230.00	6,183.00	1,953.00	129.30	3.11%	125.39
2	4,230.00	6,203.00	1,973.00	130.62	3.95%	125.66
3	4,230.00	6,297.00	2,067.00	136.85	7.21%	127.65
4	4,230.00	6,378.00	2,148.00	142.21	12.46%	126.46
5						

## MOISTURE CONTENT DETERMINATION

Can Number	1	2	3	4	5
Weight of can, g.	304.50	293.20	305.90	297.30	
Weight of Moist Soil & can, g.	715.00	879.80	857.90	857.00	
Weight of Dry Soil & can, g.	702.60	857.50	820.80	795.00	
Moisture Content, %	3.11%	3.95%	7.21%	12.46%	

MOISTURE-DENSITY CURVE



CALIFORNIA BEARING RATIO  
ASTM D 1883-93

Project : RIANG Hanger	Test No. : CBR1	Test Date : 03/20/01
Project No. : 3321	Sample No. : Sample 1	Tested by : MCH/CCP
Location : Quonset Point, RI	Sample Type : Remolded	Checked by : jdt

Soil Description : Very dark gray silty sand with gravel & organics  
 Sample Preparation : Compacted to 95% of Max Density @ 8.0% moisture  
 Remarks : ---

Height : 4.580 (in)	Sample was : SOAKED	Void Ratio : 0.33
Area : 28.27 (in <sup>2</sup> )	Piston Friction : 0.00 (lb)	Wet Unit Weight : 131.56 (lb/ft <sup>3</sup> )
Volume : 129.50 (in <sup>3</sup> )	Swell : 0.00%	Dry Unit Weight : 122.39 (lb/ft <sup>3</sup> )
Weight : 11487.00 (gm)	Surcharge : 4960.00 (gm)	


CBR at 0.1 in. : 23  
 CBR at 0.2 in. : 20  
 CBR at 0.3 in. : 17  
 CBR at 0.4 in. : 16  
 CBR at 0.5 in. : 16

	Initial	After Test	
		top 1"	average
CONTAINER NO.	jgb52	k112	new2
WT CONTAINER + WET SOIL (gm)	307.85	549.10	670.82
WT CONTAINER + DRY SOIL (gm)	287.02	488.86	614.17
WT WATER (gm)	20.83	60.24	56.65
WT CONTAINER (gm)	9.09	8.17	9.67
WT DRY SOIL (gm)	277.93	480.69	604.50
WATER CONTENT (%)	7.49	12.53	9.37


NOTE: ASTM Designation: D 1883 - 93 states that the bearing ratio reported is normally the one at 0.10 in. penetration. When the bearing ratio at 0.20 in. penetration is greater, rerun the test. If the check test gives similar results, use the bearing ratio at 0.20 in. penetration.

Results are reported for penetrations in increments of 0.1 inches. The user of these data should interpret the data to obtain a design value of CBR.

# CALIFORNIA BEARING RATIO



Symbol : O  
Project Name : RIANG Hanger  
Project No : 3321  
Sample No : Sample 1  
Test Date : 03/20/01  
Test No : CBR1  
CBR at 0.10 in.: 23



**LEGEND**


● B-15  
EXPLORATORY BORING LOCATION

Project Title: <b>RHODE ISLAND NATIONAL GUARD MAINTENANCE HANGAR</b> QUONSET AIR NATIONAL GUARD BASE NORTH KINGSTON, RHODE ISLAND		Issued for: <b>BENHAM GROUP</b>	
Drawing Number: <b>C-1</b>		Sheet <b>1</b> of <b>1</b>	
Project Number: <b>01005.0</b>		Survey Index: <b>-</b>	

No.	Revision	Date	App.

Designed By:	Drawn by:	Checked by:	Date:
JJR	JJR	JJR	22MAR01

Scale: 1"=50'



42 VALLEY ROAD  
MIDDLETOWN, RHODE ISLAND 02842  
TEL: (401) 849-0810 FAX: (401) 846-4169

**NORTHEAST ENGINEERS & CONSULTANTS, Inc.**  
A KNOWLEDGE CORPORATION™

**NE & C**

CIVIL  
ENVIRONMENTAL  
SURVEYING  
TRANSPORTATION  
STRUCTURAL  
GEOTECHNICAL  
MARINE